

BoQ Summary - Renovation of new premises, Killai Branch

Date: / /

Sub: Proposed Interior work for NEW PREMISES FOR KILLAI BRANCH Submission of approximate cost estimate - reg.

S.No.	Description of item	Amount (Rs.
1	Furnishing work	
2	Electrical Work	
3	Data cabling work	
4	Air conditioning work	
5	Bought out Furniture	
	Total	

excl taxes

Specifications and cost-estimate is submitted under the following terms:

* The Estimates does not include provision for CCTV /Fire Fighting/Alarm systems which would be taken up as per the approved/prevaling rates with the service provider
* All measurements for billing purposes will be as per joint-measurement taken after completion of site in all respects.
* Electrical /DATA wiring/Installings as per IS codes and CO Guidelines based in recent electrical audit observations in branches.
* All electrical installations to pass through RCBO only.
* Single Earthing pit to be provided for the whole premises
* All MCBs, wires, incoming-outgoing must be tagged and SLD to be provided to Bank.
* All wire endings to be properly lugged.
* Equipotential bonding- all metal parts to be provided with earthing with mechanical connections to earthing pit at minimum length, without looping.
* All materials for works as per approved makes of Bank /Brand manual.
* Lightning arrester to be provided for buildings more than 15m height..
* Branch should be provided with UPS Circuit independent of normal electrical circuit and all security gadgets should be connected to UPS Circuit.
* An Isolation Breaker should be provided outside main entrance to isolate the normal electrical circuit completely even when the Branch is closed. Only the input connection to SERVER should be provided bypassing this external isolation breaker.