

निविदा दस्तावेज/TENDER DOCUMENT
(नियम, शर्तें एवं ड्राइंग्स/Terms, Conditions & Drawings)

भाग/PART-ए/B

Financial BID / वित्तीय बोली

Interior and Allied works at B/O Opera House – Queen's Diamond, 5, Mama Parmanand Marg, Opera House, Mumbai-400004



विज्ञापन की दिनांक/ Date of Advertisement	10-06-2024
प्रस्तुत करने की अंतिम दिनांक / Last Date of Submission	02-07-2024 by 15:00Hrs
खुलने की दिनांक /Opening Date	तकनीकी बोली/Technical Bid : 02-07-2024 वित्तीय बोली: तकनीक रूप से अर्हता प्राप्त ठेकेदार को सूचित किया जाएगा/ Financial Bid: To be intimated to Technically Qualified Contractors.
कार्य अवधि/Time Period of Work	कार्य आदेश प्रदान करने की दिनांक से 90 दिन /90 days from award of Work Order
बयाना जमा राशि/Earnest Money Deposit	Rs.30,000.00 (Rupees Thirty Thousand Only) DD favoring Central Bank of India, Payable at Mumbai.
निविदा दस्तावेज का मूल्य/Cost of Tender Document(गैर वापसी योग्य/Non Refundable)	रु. /Rs.2000.00 (सेन्ट्रल बैंक ऑफ इंडिया के पक्ष में मांग ड्राफ्ट जो मुंबई पर देय हो/ DD In Favor of Central Bank of India, Payable at Mumbai or be deposited in the below account and the UTR number be uploaded
AC NO: 1001788300, IFSC: CBIN00280606, Central Bank of India Boribunder Branch, Mumbai.	
MSME Registered Vendors are Exempted from EMD and Tender Fees Relevant Documents to be submitted in Technical Bid.	
खुलने की दिनांक से निविदा की वैधता/Validity of Tender from the date of opening of Financial Bid.	90 दिन/ days
प्रस्तुत किए जाने वाले दस्तावेज/ Documents to be provided	निविदा आमंत्रण सूचना के अनुसार/As per Notice Inviting Tender.
Independent External Monitor (IEM)	Mr Trivikram Nath Tiwari MAIL ID: - trivikramnt@yahoo.co.in Mr. Jagadip Narayan Singh MAIL ID: - jagadipsingh@yahoo.com
Email for Correspondence	gadmumro@centralbank.co.in archmmzo@centralbank.co.in
संपर्क व्यक्ति का नाम/Contact person name	Mr.Manish Kumar-Senior Manager Amarnath .V – Senior Manager Architect 022-40345840/40345872/6303929013
बोलियां जमा करने का स्थान / Place of submission of Bids & opening of bids.	South Mumbai Regional Office, Ground Floor, 346 Standard Building, Dr D.N.Road, Fort, Mumbai-400023.

South Mumbai Regional Office, Ground Floor ,346 Standard Building, Dr D.N.Road, Fort, Mumbai-400023. Visit us at [http:// www.centralbankofindia.co.in](http://www.centralbankofindia.co.in)

PREAMBLE TO THE BILL OF QUANTITIES

The work proposed to be carried out at the proposed Office premises as mentioned on the cover page (page no.1) of the tender. The quality of work proposed should have ***the best workmanship***. The contractor should ensure that only the first quality materials mentioned in the list of material is purchased for the project.

1. The work should be carried out in such a way that the structure is not disturbed.
2. Any difference / discrepancies in the specification should be clarified with the Engineer in charge before submitting the tender. **The Engineer in charge will have the liberty to modify the specification to a reasonable limit to suit the basic concept during the course of work; the tenderer should carry out such work without any extra cost.**
3. **In case of any major modification such items will be considered as extra items. Payment for such items will be paid based on the Engineering rate / Market rate analysis. 15% of the total cost of material and labour will be considered as tenderer's profit.**
4. **The contractor should co-ordinate with the other contractors employed at the site for smooth flow of work.**

NOTE:

The building is occupied by the Bank. The work needs to be carried out as per the instruction of the Bank time schedule. Further, the work needs to be carried in phase wise. The Contractor should prevent the external glazing and the flooring with plastic sheets and P.O.P. sheet respectively.

1. **The contractor should obtain necessary permission from the BMC any Government Authority if required along with the security deposit amount, the security amount will be reimbursed to the contractor.**
2. The Contractor needs to clean the site on day-to-day basis.

IMPORTANT:

Rates quoted shall be deemed to be inclusive of the following general scope of items.

1. Tenderers are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their tenders as to the nature of constitution already existing (so far as in practicable), the form and nature of the site, the means of access to the site, the accommodation they may require and in general shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their tender.

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

2. **A tenderer shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charges consequent on any misunderstanding or otherwise shall be allowed.**
3. The tenderer shall be responsible for arranging and maintaining at own cost all materials, tools and plants, facilities for workers and all other services required for the execution of the work unless otherwise specifically provided for in the contract documents.
4. Submission of tender by a tenderer implies that he has read this notice and all other contract documents and has made himself aware of the scope and specification of the work to be done and of conditions and rates at which stores, tools and plants etc. if any will be issued to him by Bank and local conditions and other factors having a bearing on the execution of the work. The tenderer must also study the neighbourhood, rules and regulations for building as well as the area where it is situated.
5. Allow for Provision of all record drawings showing complete installation, structure & architectural form as installed.
6. Allow for preparation & submission of As-built drawings in soft & Hard copies along with all operating manuals, maintenance manuals procedures and all other documentation, certifications, warranties/guarantees as required
7. **Mobilization:** Mobilization of Necessary Personnel required for the works
8. **Coordination:** Allow for the comprehensive coordination of all services with other contractors, clients, building maintenance team, security
9. **Cleanliness:** To maintain the site clean throughout the project & final professional cleaning of the site
10. **Scaffolding:** Necessary Scaffolding to Carry out the Works including additional high scaffolding for ceiling Works
11. **Insurance:** Maintaining approved insurance as required equal to contract value
12. **Protection:** Protection of existing finishes while working
13. **Municipality Liaisoning Works:** Allow for Liaisoning Works with Municipality & Preparation of all Necessary Drawing for Obtaining Approvals from Concerned Authorities Excluding any Fees, Deposits, Charges for the same. The contractor should obtain all required approvals before the start of the works.

14. Shop Drawings

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

- a) Allow for preparation of Shop Drawings for:
- b) Furniture, Plumbing & Drainage
- c) Architectural & Finishes
- d) Builder's work Drawings
- e) **Drawings portfolio to be approved before commencing of works on site the total completion period of the project is inclusive of this item. Drawings are to be provided as per the attached annexure.**

BILL OF QUANTITIES:

1. Rates to be quoted by the tenderers in the item rate tender in figures and words shall be accurately filled in, so that there is no discrepancy in the rates written in figure and in words. However, if a discrepancy is found between the rate written in figures and rate written in words then the rate which correspond with the amount worked out by the contractor shall be taken as correct.
2. If the amount of an item is not worked out by the tendered, or it does not correspond with the rate written either figures or in words, then the rate quoted by the tenderer in words shall be taken as correct.
3. Where the rate quoted by the tenderer in figures and in words tally but the amount is not worked out correctly, the rate quoted by the contractor will be taken as correct, not the amount.
4. The work needs to be carried out as per the time schedule instructed by Bank.
5. All other office furniture, office equipment, flooring, false ceiling etc. to be cover with plastic sheet or required packing materials
6. Any damages done by the contractor will be recover from the contractors.
7. Cleaning to be done on day-to-day basis.
8. Electrician and one supervisor should be posted in working day to avoid any office disturbance and maintain the office smoothly.

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 4

SUMMARY OF BILL OF QUANTITIES

PART	DESCRIPTION	AMOUNT (Rs.)
A	LOOSE FURNITURE	
B	<i>FIXED FURNITURE</i>	
	TOTAL	
	ADD GST AS APPLICABLE	
	GRAND TOTAL INCLUDING GST	
<div>(RUPEES IN WORDS): <div></div>ONLY</div>		

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

PART A: LOOSE FURNITURE

Bill of Quantities					
S.No.	Details of works.	Quantity	Unit	Rate	Amount
	(Particulars)			(Rs.)	(Rs.)
	GENERAL: All Tables / counters/ work stations to have 19mm Ply block board top & sides, and apron/front modesty 12 mm comm. Ply/board .Unless otherwise specified, all external/exposed surfaces shall be provided with1.0 mm laminate finish and all internal surfaces shall be painted with white/ivory shade of satin finish enamel paint of approved make. Drawer/side storage units to be made from 12mm /19mm ply, with steam beach/teak wood lipping on edges. The drawers to run on telescopic drawer channels of approved make. Drawer units to have two smaller and one bigger drawers and locking arrangement (Godrej or equivalent). Foot-rest 75x50mm 2nd class cedar wood member to be fixed for each table the rate to include all hardware such as drawer channels, SS handles etc. The item also includes a tray for key board running on telescopic channel, finished with laminate on top and rounded front size 560x450 readymade EBCO make CPU trolley with castors etc. complete. In case of curved shape of table / counter, length at the center of the top shall be measured for payment.				
1	B.M. 'S TABLE	1.00	Nos.		
	Providing and fixing Branch Manager Table as per main specification but finished in 1 mm laminate in two or more colors. Table top fixed with glass of approved thickness on metal SS studs.).The table size to be 6'-0" x 3'-3" x 2'-6" & storage unit 3'-0" x 2'-0"				
2	OFFICER'S TABLES	7.00	Nos.		
	Providing and fixing Officer/Manager				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 6

	Table as per main specification but finished in 1 mm laminate in two or more colors. The table front provided with laminate on S.S Studs (Size 135 x 60MM aprox.). The table size to be 5'-0" x 2'-6" x 2'-6" & storage unit 3'-0" x 1'-4" Table top fixed with glass of approved thickness on metal SS studs.).				
3	SWO COUNTERS	5.00	Rft		
	Providing and fixing SWO Table as per main specification but finished in 1 mm laminate in two or more colors The table front provided with laminate on S.S Studs (Size 135 x 60 mm aprox.). Counter items also includes Front modesty with 19mm Commercial ply with laminate. Drawer units to be as specified in MAIN specifications. BUT with divisions for currency as per BANK's instructions, The drawer units to have AUTOLOCKING system for drawers (Godrej). One footrest per occupant, key board tray 560x450 and CPU stand. All as per MAIN Specifications for tables. Inside of the counter & drawers shall be painted with satin finished enamel paint of approved make and ivory/white shade etc, complete to the satisfaction of Architect/Bank. The storage unit to comply to specifications as stated for officer tables. The table size to be 5'-0" x3-1" x 2'-6" & storage unit 3'-0" x 1'-6". The counter shall have the Work top and counter top as per design similar to cash counter stated in item 4 with 300m wide granite(basic rate of granite Rs.225) adhering to specifications as stated.				
4	CASH COUNTER	5.00	Rft.		
	Providing and placing in position Cash Counter Table made from 19mm Commercial ply/Block Board and with 1mm laminate finish, with overall height of 1050 mm for working counter at 750mm height made from 18mm pre-polished 300mm wide granite over 19				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 7

	mm commercial ply/ block board. And customer counter at 1050 mm height made from 12mm thick beveled glass placed over 300mm high, 12mm theatrical, frosted toughened glass. Front modesty with 19mm Comm. Ply/Board finished in 1 mm laminate. The Counter to have drawer units same as mentioned in Main specifications of Tables above except the drawers to have divisions as per Bank's instructions. The counter to have 1 footrest per occupant. Item also includes a key-board tray & C.P.U. stand of EARL Bihari make Inside of the counter & drawers shall be painted with satin finished enamel paint of approved make and ivory/white shade etc., complete to the satisfaction of Architect/Bank. The table size to be 5'-3" x 3'-1" x 2'-6" & storage unit 3'-0" x 1'-6".				
5	GLASS RAILING	200.00	Sq.Ft.		
	Providing and fixing 12mm Etched float glass (straight or bent as per shape given in plan) in front of Cash Cabins and SWO with metal clamps/D brackets /S.S. Studs or Wooden supports including cutouts for passing currency as per details The edges of the glass to be polished complete with necessary cutting the holes in shape properly, grinding & polishing. The glass may be fixed in vertical or inclined position as per given drawings.				
6	SERVER ROOM COUNTER	5.00	Rft.		
	Providing and fixing Server Table including drawer units with same specifications as main table. The table size to be 6' x 5'-6" x 2'-6" (Ref Layout plan) general specifications for tables to be adhered.				
7	STORAGE CUPBOARDS				
	GENERAL : All storage cabinets/ low height cabinets/side racks shall have 19mm Ply/ block board for box, shelves and shutters				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 8

	and 6mm ply for back. Unless otherwise specified, all external/exposed surfaces shall be provided with 1.0 mm laminate finish of approved make and design and all internal surfaces shall be painted with white/ivory shade of satin finish enamel paint of approved make. All edges of ply/block board shall have 25x12mm teak wood/ steam beach lipping. The cabinet shall have self-closing hinges, (Godrej, Ebco, Hettich), SS handles, magnetic catchers, godrej /equivalent locks etc. complete - as/drawing details to the satisfaction of Architect. The front area of cabinet i.e. length x height shall be measured for payment.				
a	FULL HEIGHT CABINETS	400	Sft		
	Providing & fixing box fill height cupboards 400/450mm deep & height 2100/2400 mm as per main specifications mentioned above.				
b	LOW HEIGHT STORAGE	80	Sft.		
	Providing & fixing low height cupboards 400/450mm deep & height 750/900 mm as per main specifications mentioned above.				
8	SIDE RACKS	40	Sft.		
	Providing & fixing side racks 400/450mm deep & height 750/900 mm as per main specifications mentioned above.				
9	DAFTARI TABLE	1	Nos		
	Sub staff unit made of 18mm plywood structure and 2 numbers of drawers, finished with 1mm thk laminate on exposed surfaces and teakwood beadings with all hardware and accessories etc. Unexposed surfaces finished with enamel paint with edge beadings neatly polished. Size : 5'0"x2'0"x2'6"				
10	WRITING DESK	1.00	Nos.		
	Providing and fixing writing desk, using 10 mm beveled clear glass top over 19 mm ply base +1mm Laminate on all exposed surfaces of ply ,with pigeon holes of 6"x6" to keep slips, approx. size 4'0" x 1'6" x				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 9

	0"8" , to be fixed at 3'6" height				
11	DROP BOX/COMPLAINT BOX	2.00	Nos.		
	Size 3'3"L X1'0"Wx 2'6' H , to be made from 19mm thick MR Grade plywood and finished with 1 mm thick laminate outside, with steam beach/teak wood border/lipping on exposed edges as per design and drawing and inside shall have enamel paint. The drop box will have 3 internal (vertical) divisions for Local, Out station and Credit card payment cheques etc. with 3 open able shutters on front with lock. Front / Top shall have 3 nos. 6" long x 1" wide slits to drop letter / cheque etc.				
12	NOTICE BOARD /BRAND WALL	200.00	Sq.Ft		
	Providing & fixing on partition/ walls soft pin-up board as per following specification. Core material of 10mm thick soft board finished with approved fabric. Framed with teak wood of section 2"x1.5", Approx. board size 4'x2'-6".				
	MISCELLANEOUS WORK				
13	VERTICAL BLINDS	200	Sq.Ft.		
	Providing & fixing as per approved sample 100mm wide vertical fabric blinds complete with handing chain. Sliding and tilting system in drawn position. Fabric veins to overlap by minimum 10mm (every 1.0 metre running length to have at least 11 Nos. 100mm wide fabric veins). Length of the blinds as mentioned in drawings bottom end to be at least 12mm from horizontal surface. Fabric strip, as that of fabric vein, to be fixed on both sides of aluminum top channel. Lower ends of blind to be weighed down and tied with each other on both corners, with ball chains. Item to be complete in all respects including fixing with bracket on wall or partition with raw plugs.				
14	FROSTED FILM	250	Sq.ft		
	Supply of frosted film in approved designer pattern over glass as per design to manufactures specification and				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 10

	engineer in charge instructions.				
	SUB TOTAL OF PART A :				
Sno	Details of works.	Quantity	Unit	Rate	Amount
01	(Particulars)			(Rs.)	(Rs.)
	GENERAL : For Partitions : All partitions shall have a frame work of saal / kail/chill wood size 50x35 or 50x50 mm at spacing not exceeding 600mm c/c in both directions as per requirement with 6mm ply on both faces including grooves, with / without 1mm thick laminate of approved make and design, up to 750/900/1200/1500/2100/ 2400mm height and clear transparent/frosted/etched glass of 5/9mm thickness shall be provided above the height of 750/900mm as per drawings and details . Vertical members for framing shall be continuous/ one piece i.e. without joint. The rate to include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc, making provision for laying conduit as per drawings and directions of site Eng. / Architect. All wood frame work to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti-termite properties. The work also includes doors with door closers /flap doors as per requirements along with all locks (Godrej or equivalent) Handles, Hinges, stoppers etc. as per bank's architect instructions Measurement of height shall be taken from finished floor level up to the bottom level of false ceiling, In case of varying heights on either side of partition, average heights shall be considered.				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 11

	<p>For paneling : All paneling shall have a frame work of saal / kail/chill wood size 50x25 or 50x35 mm at spacing not exceeding 600mm c/c in both directions as per requirement with 12mm ply on both faces including grooves, with / without 1mm thick laminate of approved make and design, up to 750/900/1200/1500/2100/2400mm height . Vertical members for framing shall be continuous/ one piece i.e. without joint. The rate to include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc, making provision for laying conduit as per drawings and directions of site Eng. / Architect. All wood frame work to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti-termite properties. The paneling may also include approx. 1'6" x2'6"size soft board/s with melamine polished steam beach/ teak wood border & fabric for display of notices etc.as shown in drawing. Measurement of height shall be taken from finished floor level up to the bottom level of false ceiling, In case of varying heights on either side of partition, average heights shall be considered.</p>				
a	LOW HEIGHT PARTITIONS	160	Sq.Ft.		
	<p>Providing and fixing Low height partition from floor level up to the 1220 /1530mm as per main specifications mentioned above.1.0mm thick laminate of approved make and design to be fixed on both faces over 6mm thick ply. Partition to have a 75x20 mm th. melamine polished cedar/steam beach/teak wood molding on top and side edges of partition.9 mm thick plain/etched glass above 900 mm height in taper or curved shape as detailed shall be fixed with steam beach/ teak wood beading of 25x12 size.,</p>				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 12

	complete with polishing/paining the grooves as per design and to the satisfaction on Architect / Bank. The low height partitions shall include flap doors with required hardware and fittings. The partition shall also include apprx.2'0"x 1'6" size soft board/s with fabric for display of notices etc.as shown in drawing.				
b	PARTLY GLAZED PARTLY LAMINATED WOODEN PARTITION	340	Sq.Ft.		
	Providing and fixing partly Glazed Partition partly laminated wooden as per main specifications mentioned above up to bottom of false ceiling. Item also includes 5mm clear transparent Etched Glass above 900 mm to 2100 mm fixed in 35x20 mm cedar/steam beach/teak wood beading fixed around opening finished with melamine matt finish polish. Rest of specifications same as MAIN specifications of Partitions. etc. complete to the satisfactions of Architect/ Bank.				
c	FULL HEIGHT , BOTH SIDES LAMINATED	320	Sq.Ft.		
	Providing and fixing partition from floor level up to the level of false ceiling as per main specifications mentioned above, including 6 mm thick ply + 1mm thick laminate of approved make and design ,to be fixed on both sides, including grooves , the exposed cedar/steam beach/teak wood surfaces with melamine polish as per design etc. complete and to the satisfaction of Architect/bank.				
02	PANELING AROUND COLUMNS/WALLS	360	Sq.Ft.		
	Providing and fixing wall paneling as per design & pattern with 50x25mm Kail/ Saal wood frame at 2'-0" c/c in both directions with 12mm Commercial ply on top and finished with 1.0 mm laminate. Over the paneling 1'6" x2'6"size soft board/s with melamine polished steam beach/ teak wood border of size as specified by the				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 13

	architect & fabric for display of notices etc.as shown in drawing. Also at top, middle and bottom level a decorative border of melamine polished, 100x25/75x25 size cedar / steam beech as per design and details shall be fixed.				
03	ENTRANCE DOOR (incl. Floor Spring)	230	Sq.Ft.		
	Providing and fixing glass door for entry with 3" X 3" beach frame wood work duly fixed with the partition/wall with hold fast duly polished. A white beach wood frame work size 6" X 2" as top and bottom rail with a decorative handle of 600mm of approved brand, floor spring, Locks, etc., all complete. 4" X 2" thick stiles to be fixed on the frame 3 sides. 12mm thick etched glass and Central bank logo frosted design with necessary and blasting/granular blasting to be provided and edge should be machine beveled polished. The work to be completed as per design and specification of the Architect all complete. The wooden portion to be duly melamine polished. by the architect. The door shall be inclusive of and fixed on floor spring of ISI approved make such as Godrej/Everest / Everite / Efficient Gadget etc. complete.				
4	Wooden frame GLASS PARTITION	120	Sq.Ft.		
	NOTE: Quantity to include full height glass part ion on the entrance. compiling to specifications as in item 6				
5	PAINT WORK				
a.	ACRYLIC EMULSION PAINT	6000	Sft.		
	Painting two or more coats with acrylic emulsion paint of Asian (Royale),I.C.I.(Velvet Touch) brand, or equivalent to give an even shade, including one or more coats of lime/cement based putty and primer, on the walls of banking hall, manager's cabin, meeting room, server room etc. Surface to be cleaned, sanded, leveled and repaired, on old and new work.				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 14

b	SYNTHETIC ENAMEL PAINT	1000	Sft.		
	Painting two or more coats with synthetic enamel paint of approved brand, shade & manufacture to give an even shade including one or more coats of putty and primer. Surface to be sand paper cleaned and prepared; on inside of rolling shutters, grills, etc., on walls/partitions/furniture as directed by the architect/bank.				
c	SYNTHETIC ENAMEL PAINT WITH LOGO	200	Sft		
	Painting two or more coats with synthetic enamel paint of approved brand, shade & manufacture to give an even shade including one or more coats of putty and primer. Surface to be sand paper cleaned and prepared; on outside of rolling shutters with design/ logo of C.B.I., painted as directed by the architect/bank.				
d	APEX PAINT OUTSIDE	500.00	Sft		
	Painting two or more coats with acrylic based exterior paint of approved brand & manufacture (apex or equivalent), with given colour scheme to give an even shade including one or more coats of suitable putty and primer. Surface to be sand paper cleaned and prepared; on outside of building walls, as directed by the architect/bank.				
6	FALSE CEILING :	900	SFT		
	<p>Providing and fixing in position suspended false ceiling consisting of the following G.I. sections manufactured by M/s. India Gypsum Ltd.</p> <p>Vertical suspenders of angle section, peripheral channels, primary and secondary frame work at center to center distance of 450mm to 600 mm center to center and C channel to be fixed with top R.C.C. ceiling as per the site requirement and minimum distance of 900mm center to center and all as per the India Gypsum Technical Specification maximum of 'C' channels, the suspenders to be fixed with</p>				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 15

	the ceiling with the help of angle cleats and expansion bolts. The peripheral channels to be screwed to the wall with the help of metal screws, the junction of peripheral channels and primary / secondary channels to be screwed with suitable metal screws. The junctions of primary and secondary channels to have G.I. clips. Providing and fixing 12 mm thick double skin gypsum board manufactured by M/s. India Gypsum Ltd. to the frame work with the help of suitable screws in line and level. The item also includes providing false ceiling in stepped design. The joints of the boards to be finished with bonding paper. Providing and applying 2 coats of gypsum primer to the entire surface and finish the same with putty work etc. so as to be ready to receive paint. The false ceiling will be in stepped design. The actual visible area will be measured and paid. This item includes necessary cut out for the electrical and other service.				
7	GYPSUM DROP CEILING	600	SFT		
	As per design with vertical drops and curves. Specification of item no 9 to be adhered.				
8	GRID CEILING:	800	SFT		
	ARMSTRONG CEILINGS – ALY-IN PERFORATED MICROLOOK EDGE METAL TILE WITH ACCOUSTICAL FLEECE WITH XL 15MM GRID: Providing and fixing in Armstrong mineral Fibre Acoustical Suspended Ceiling with ULTIMA (MICRO LOOK) EDGE TILES WITH ARMSTRONG SILHOUTETE EXPOSED GRID. The tiles should have Humidity Resistance (RH) of 95% NRC 0.75, Light reflectance 90%, Thermal Conductivity K=0.57, w/m.K, Sound Attenuation of 37 DB, Colour White, Fire Performance A2-sl.d0 in module size 600 x 600 x19mm with Bio Block coating on the face of the tile,				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 16

<p>suitable for Green Building Application with Recycled content of 70-80%.</p> <p>The tile shall be laid on Armstrong Silhouette profile grid System with 15mm white flanges incorporating a 6mm central reveal in white/black color. Silhouette, Main runner & Cross Tees to have mitred ends and birds mouth notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 120 grams per M2.</p> <p><u>INSTALLATION</u></p> <p>To compromise main runner spaced at 1200mm centre securely fixed to the structural soffit using Armstrong suspension system (Specifications below) at 1200mm maximum centre and not more than 150mm from spliced joints. The First/Last Armstrong suspension system at the end of each main runner should not be interlocked between main runner at 600 mm centre to form 1200 x 600 mm module. Perimeter trim to be Armstrong wall angles, secured to walls at 450mm maximum centre.</p> <p><u>ARMSTRONG SUSPENSION SYSTEM:</u></p> <p>Accessories manufactured and supplied be Armstrong World Industries consisting of M6 Anchor Fasteners with vertical Hangers made of Galvanized Steel of size 26 x 26x 25x 1.2mm with a Galvanized Thickness of 80gm/Sq.m, A per straightened Hanger wire of dia-2.68mm of 1.83m length, thickness of 80g/sq.m and tensile strength of 344-413 MPa, along with adjustable hook clips of 0.8mm thick galvanized spring steel for 2.68 with minimum pull strength of 110Kg. The adjustable clip also consist of a 3.5mm aquiline wire to be used with the main runner-2.68mm of 1.823m length, thickness of 80g/sq.m and tensile strength</p>				
--	--	--	--	--

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

Page 17

	of 3434-413 MPa , along with adjustable hook clips of 110 kg.Teh adjustable clip also consist of a 3.5mm aquiline wire to be used with the main runner. All complete as per drawing and details & direction of Engineer-in-charge.				
	The item includes providing necessary electrical, AC and other service cutout etc				
	SUB TOTAL OF PART B :				

Confirmation of Acceptance of Tender terms and conditions

(To be signed by the bidder and enclosed along with their offer in a separate envelope)

We have studied the terms and conditions of Tender Enquiry including General and Special terms and conditions, the specifications, lay-out drawings, Schedule of Quantities, Commercial terms and conditions, Approved Makes, etc.

We are accepting all terms and conditions of the Tender without any deviation.

Offer with any deviations from the Tender Enquiry are likely to be rejected.

We also understand that the order / s will be placed in the name of principals only and not in the name of their dealer/s. Our quotation is based on the above.

Date: _____

SIGNATURE OF TENDERER

WITH RUBBER STAMP

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

DECLARATION

I / We hereby declare that I / We have read and understood the Terms and Conditions of the contract, Specifications, Drawings, Schedule of Quantities etc. and hereby agree to abide by them. In token thereof, I / We have signed below and at the end of the Schedule of Quantities, failing which the tender is liable to be rejected.

I / We understand that our Tender will not be considered if the rates for items are not written both in FIGURES and WORDS.

I / We hereby confirm that only the relevant entries asked for, have been made within the Tender documents issued to us. I / We also confirm that in the event of any entry in this Tender document other than the relevant entry or condition shall make this Tender invalid.

Date : _____

SIGNATURE OF TENDERER

WITH RUBBER STAMP

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP