

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

ALL ITEMS IS TO BE MADE AT SITE AND WOODEN RAW MATERIALS SHOULD BE GOT CHECKED BEFORE PASTING LAMINATES. NO FURNITURE ITEMS SHOULD BE MADE IN FACTORY / WORKSHOP

SPECIAL NOTE: ALREADY FEW INTERIOR & ELECTRICAL WORKS HAVE BEEN EXECUTED AT ABOVE BRANCH PREMISES. CONTRACTOR SHOULD WORK IN COORDINATION WITH THE OTHER AGENCIES WORKING THERE WITHOUT CAUSING ANY DAMAGE TO THE WORK ALREADY EXECUTED.

CIVIL & INTERIOR WORK PART-I					
S.No	Item/Description	Qty.	Unit	Rate	Amount
1 A	<p>Partition & Panelling works (only with HDHMR/EDHMR boards– Century/ Greenply/Archidply). All woods to be treated with anti-termite coating (all sides).The thickness of plyboards/plywoods mentioned below is for boards without laminates</p> <p>(Specification for item from 1A to 1G).</p> <p>Measurement of height shall be taken from finished floor level up to the level of false ceiling in case of full height partition. In case of low height the measurement of height shall be taken from FFL upto the beading top. In case of varying heights on either side of partition, average heights shall be considered. The rate to include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc, making provision for laying conduct as per drawings and directions of site Eng. / Architect. It also includes teak wood properly polished / laminated top beading on all sides as per the requirement of specified size as per the directions of Engineer. All wood frame work to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti-termite properties. The work also includes provision of door as per requirements along with all lock (Godrej) Handle, Hinges (5.5) stoppers, door closures etc. as per bank's architect instructions. The rate also includes at no extra cost providing extra framework support above false ceiling upto RCC slab at every 4ft or less distance so as to make entire full height solid/glazed/semi-glazed partition rigid and firm.</p> <p>1 A - Providing and fixing solid partition / glazed partition from floor level up to the level of false ceiling with frame work of aluminum with sections 1.75" x 1.75" at spacing not exceeding 600mm center to center in vertical direction. (Vertical member to be in one piece) and horizontal direction with 7 mm or more thick boards to be fixed on both sides, including grooves as per instructions and 1.0 mm thk laminate to be fixed (both sides) on top complete with polishing / painting the beading surafce with spirit polish as per design and to the satisfaction of Architect/Employer. For glazed partition – item also includes 10mm Etched/frosted Glass above 900 mm to 1350/1800/2100/2400/2700 mm fixed in 75x15 mm beading as per specifications fixed around opening finished with melamine matt polishing/laminate. Rest of specifications same as MAIN specifications of Partitions. Complete to the satisfactions of Architect/ Bank.</p>	285	Sqft.		
1 B	1 B - Providing and fixing Low height partition from floor				

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

	level up to the 1220/1540 mm with frame work of aluminium 1.75" x 1.75" at spacing not exceeding 600 mm center to center in vertical direction (Vertical member to be in one piece) and horizontal direction, 7 mm or more boards to be fixed on both sides, including grooves as per instructions and 1.0mm thick laminate to be fixed on top. 15 mm teak wood moulding on top and side edges of partition and including 12 mm etched glass above 900 mm in straight / taper or curved shape as detailed, complete with polishing/painting the grooves as per design and to the satisfaction on Architect / Bank.	80	Sqft.		
1 C	1 C -Providing and fixing wall panelling as per design & pattern with atleast 1.5"x 1" aluminum frame at 2'-0" c/c in both directions with 7mm or more thick boards on top and finished with 1.0 mm laminate. The panelling to be screwed to the frame work; as per design and details. The wood surfaces to be finished in melamine polish complete. Top of the paneling edges / is to be provided with laminate or teak wood decorative beading of 35mm x 15 mm finished with polish/painting as directed.	350	Sqft.		
1 D	1 D - Providing and fixing cash cabin partition from floor level up to the level of 2100 mm (approx.) with same specification as above at serial no. (a), (b) but with a 12 mm thick etched glass / tapered glass from 1067 up to 2100 fixed in teak wood beading of the size 35x15 mm over aluminum frame of size 10x25 screwed to the frame work: as per design and details. The wood surfaces to be finished in melamine polish complete. The item also includes cash cabin door with required hardware, accessories, door closure, handle, lock etc. which will be measured as partition.	100	Sqft.		
1 E	1 E - Providing and fixing 12mm toughened glass partition in FRONT of CASH CABINS with metal clamps and all required accessories over existing partition including cutouts for passing currency as per details in item no. 1 (f). The edges of the glass to be polished complete with necessary cutting the holes in shape properly, grinding & polishing.	25	sqft		
1 F	1 F - FULL HEIGHT 12MM THK. TOUGHEN GLASS PARTITION: P/F 12 mm thick toughened glass full height glass embedded in aluminum anodized sections all around for external / internal glazing. Anodizing to be Natural Finish shade. (as per Bank's approval).(Frame work details as mentioned in item no. 1 above) The works includes fixing of glass with Top & Bottom surfaces with proper support/frame. The work also includes providing and fixing glass film (3M brand or equivalent) as per the design approved by Bank's Engineer-In-charge.	170	sqft		
1 G	1 G - ACP wall panelling: Providing & fixing in position Aluminum composite panel (ACP) with framing of Aluminum tube sections of min 1.5" x 1" and 20 gauge 2'0" c/c both ways.ACP to be in 2' width panels or distributed equally. Panels to be fixed to the frame with 3M or equivalent adhesive and with mirror screws. Joints to be finished with silicon based sealant. ACP thickness of 3 mm minimum. Aluminum foil thickness to be min 0.20mm on both sides. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brand to be used. Bright silver Shade to be as per bank's architect approval.	240	sqft		

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

	Additional sections to be provided wherever necessary to fix the Indoor AC units as per site requirements. Both the AC units to be installed at location as per Bank's approval near the machine area at the highest position.				
2 A	Providing and fixing of toughened glass doors (min. 12mm) with below fixtures of size 1050x 2100 mm (approx.)	1	Nos		
	Door Lock				
	Door stopper				
	Floor Machine (design as per load) - Ozone, Hardwyn, Dorset				
	Parch fitting				
	S.S. Handle 12" long (both sides)				
2 B	Providing and fixing (FLUSH DOOR) – Doors- Providing and fixing solid flushed door / glazed door having specification as solid / glazed partition in item no. 1 (a) min 35mm thick finished on both sides with 1.0mm thick laminate of approved shade as indicated in drawing. Shutter to be lipped on all sides with 12mm thick teak wood beading. Applicable hardware to be considered for following doors according to requirement as per detailed drawings including below mentioned hardware-Door closer,SS Ball bearing Hinges ,SS foot operated Door stopper,SS Mortise Latch Lock / concealed dead lock,SS Mortise Handle. All material is of approved brand. approx size of door 750 x2100	2	Nos		
2 C	Flap door: P/F 4' x 3' matching 19mm laminated plyboard flap door.	1	Nos.		
3 A	ACP Shutter Box: Rolling shutter boxing made up in ACP (min 3mm thick) with required frameworks with all accessories as per Architects approval. Measurement to be considered for all sides for work complete in all respect.	55	sqft		
3 B	ELECTRICAL CABINET(all inside structure only with HDHMR/EDHMR boards– Century/ Greenply/Archidply; for shutters 19mm plyboard with Greenply (ecotec) / Century (sainik) / Archidply (classic)): Providing and fixing the 1'-6" deep storage units. The storage units shall have shutters made in 17mm or more thick boards and finished in laminate of approved shade including top. Laminate to be provided in 1 mm thickness (exterior) and 0.8 mm thick (interior)- no paint. Backply to be in 7 mm or more boards.The storage units shall have intermediate shelves as per DB sizes made in 17mm or more thick boards with matching wood lipping. The storage shall have matching wood edge molding as per the detail drawings. This also includes providing necessary hardware like handles, hinges, locks, tower bolts etc. of approved make. All exposed wooden surfaces shall be stained to shade. Louvers to be provided in shutter as per the design / instructions of Bank.	40	Sqft.		
3 C	FILE STORAGE CABINETS(all inside structure only with HDHMR/EDHMR boards– Century/ Greenply/Archidply; for shutters 19mm plyboard with Greenply (ecotec) / Century (sainik) / Archidply (classic)): Providing and fixing the 1'-6" deep storage units. The storage units shall have shutters made in 17mm or more	500	Sqft.		

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

	thick boards and finished in laminate of approved shade including top. Laminate to be provided in 1 mm thickness (exterior) and 0.8 mm thick (interior). The storage units shall have intermediate shelves in 17mm or more thick boards with matching wood lipping. Backply to be in thickness 7mm or more thickboards. The storage shall have matching wood edge molding as per the detail drawings. This also includes providing necessary hardware like handles, hinges, locks, tower bolts etc of approved make. All exposed wooden surfaces shall be stained to shade. All exposed wooden surfaces shall be stained to shade. (same for Over Head storage required above Pantry counter.)				
3 D	CHEQUE DROP BOX :(2'-0" x 3ft High X 10" deep) Providing and fixing cheque drop boxes made out of 19mm thk. Commercial plywood grade I finished with 1mm thk. Laminate. Slit should be provided to drop cheques and opening provided with locking arrangement to remove cheques, complete in all respect.	1	Nos.		
3 E	WRITING TABLE: Writing desk made of wood with glass top as per Design Size: 3'0"X1'0" minimum. Writing Ledge to have facility of pigeon holes beneath to place the pay in / payout slips etc.	1	Nos.		
4 A	<p>FURNITURE - (specifications for items from 5A to 5D) [only with HDHMR/EDHMR boards– Century/ Greenply/ Archidply} . All Tables / counters/ work stations to have 17mm or more thick boards top and sides to be with 17 mm or more boards and 1.0 mm laminate finish on exposed surfaces with 0.8 mm thick laminate inside/all the surfaces instead of painting the surfaces / area, drawer units is to be made from 17 mm or more one side boards with 1.0 mm laminate finish. The drawers to run on telescopic drawer channels. Drawer units to have two smaller and one bigger drawers and locking arrangement (Godrej, ozone, dorma). Foot-rest 75x50mm 2nd class cedarwood member to be fixed for each table the rate to include all hardware such as drawer channels, SS handles etc. The inside of the table to be provided with 0.8 mm thick laminate (White cream shade). The item also includes a tray for key board running on telescopic channel (ozone/hettich), finished with laminate on top and rounded front size 560x450 readymade CPU trolley with castors etc. complete. (EBCO make).</p> <p>All Tables / counters/ work stations to have 17mm or more thick boards top and sides to be with 17 mm or more boards and 1.0 mm laminate finish on exposed surfaces with 0.8 mm thick laminate inside/all the surfaces instead of painting the surfaces / area, drawer units is to be made from 17 mm or more thick boards for the front and rear, 11 mm or more boards for sides and 7mm or more thick boards for the bottom with 1.0 mm laminate finish. The drawers to run on telescopic drawer channels. Drawer units (approx. size-400x450x680) to have two smaller and one bigger drawers (or storage below one drawer as required by Bank) and locking arrangement (Godrej, ozone, dorma, hettich). Foot-rest 75x50mm 2nd class cedarwood member (polished) to be fixed for each table the rate to include all hardware such as drawer channels, SS handles etc. Front modesty with 17 mm or more</p>				

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

	<p>thick boards and 1 mm laminate as per designed in straight / curved shape. The inside of the table to be provided with 0.8 mm thick laminate (White cream shade). The item also includes a tray for key board running on telescopic channel, finished with laminate on top and rounded front size 560x450 readymade CPU trolley with castors etc. complete. (EBCO make)</p> <p>(above specifications are for items from 4A to 4D)</p> <p>Item 4A - Providing and fixing Manager Table as per main specification but finished in 1 mm laminate in two or more colors. The table size to be 1800x750x750 mm. The item also includes Side cupboard for B.Manager with Laminate finish as per the specifications / design by Bank with size 900x450x750.</p>	1	nos		
4 B	<p>4B - Providing & placing in position BANKING COUNTER TABLE with 750 high x 750MM wide made of 17 mm or more thick boards working top front in straight / curved shape and 1.0 mm laminate finish on exposed surfaces with 0.8 mm thick laminate inside/all the surfaces instead of painting the surfaces / area. Counter items also includes Front modesty with 17 mm or more thick boards and 1 mm laminate as per designed in curved shape as shown in drg. Drawer units to be as specified in MAIN specifications. BUT with divisions for currency as per BANK's instructions, The drawer units to have AUTOLOOKING system for drawers (Godrej). One footrest per occupant, key board tray 560x450 laminate finish, CPU stand All as per MAIN Specifications for tables, counter is finished with 0.8 mm thick laminate (white/cream) inside the counters & drawer units etc, complete to the satisfaction of Architect/Bank.</p>	30	Rft		
4 C	<p>4C - Providing and placing in position Cash Counter Table made from 17 mm or more thick boards and with 1mm laminate finish, with overall height of 1050 mm for working counter at 750mm and customer counter at 1050 mm height made with 300mm wide 19 mm comm board finished in 1 mm laminate. Counter items also includes Front modesty with 17 mm or more thick boards and 1 mm laminate as per design. The Counter to have drawer units same as mentioned in Main specifications of Tables above except the drawers to have divisions as per Bank's instructions. The counter to have 1 footrest per occupant. Item also includes a key-board tray & C.P.U. stand for EARL Bihari/ ebcomake. The inside of the table to be 0.8 mm thick laminate (white/cream) complete to the satisfaction of Architect/Bank.</p>	5	Rft		
4 D	<p>4 D- SERVER ROOM TABLE (Size - 1200 x 700 x 750): All as per MAIN Specifications for tables / counter without drawers complete to the satisfaction of Architect/Bank. No Storage drawer is to be provided.</p>	1	Nos		
Total (Civil & Interior) =					

BOQ SPECIFICATIONS OF ELECTRIFICATION, DATA CABLING AND ALLIED WORKS PART-II

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
------	------------------------	-----	------	------	--------

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

	1	ATM DISTRIBUTION BOARD Supply, Installation, Testing and commissioning of the surface / recess mounting following way MCB three phase distribution board for single phase outgoing with IP 42 protection , direct on wall incl. the followings accessories. INCOMER 1 No. 63Amp DP MCB, 1 no. 63Amp. DP RCBO, 30mA, 16KA, C-curve OUTGOINGS 3Nos SPMCB 20A SP MCBs, 1 no. 10A SP MCB, 1 no. 10A digital weekly programmable timerswitches similar to MDS REX (2000) SET AS ABOVE incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.	1	No.		
	2a	U.P.S. DISTRIBUTION BOARD (specification from 2A to 2B) - Supply, Installation, Testing and commissioning of the surface / recess mounting following way Double door MCB D.B.- Single phase distribution board (Consumer unit) for single phase out going with IP 42 protection incl. the followings accessories – incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed. INCOMER 1 NO 63A DP MCB OUTGOINGS 2 Nos- 63Amp DP MCB SET AS ABOVE	1	Nos.		
	2b	<u>UPS DIST. BOARD OUTGOINGS.</u> 1 NOS 12 WAY SPN DIST BOARD or Bigger Size as per Requirement 1 Nos- 60 Amp DPMCB 10 NOS 10/16 AMP SPMCB SET AS ABOVE	1	Nos.		
	3	<i>SPECIAL POINTS: (UPS) any length(TO WORKSTATIONS)(Maximum TWO points in one circuit)</i> Supply, fixing, testing and commissioning of following Modular type switch socket with cover plate , sheet steel box etc on surface / concealed manner I/c electrical wiring with 2 X 2.5 sq mm + 1 X 2.5 sq mm FRLS PVC	14	Nos.		

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

		insulated copper conductor single core multi stranded wire in rigid MMS grade PVC conduit with conduit accessories like bend, junction box etc on surface / recessed manner etc (Wiring from D.B. / Source to Board/destination) and making good all the damages, painting, cleaning the site etc complete as required as per site requirement and as directed.				
		1 Nos. 16 A Switch + 3 Nos. 6 A, 5 pin Socket.				
	4	EARTHING: Copper Chemical Earthing - Supply, Installation, Connection, Testing and Commissioning of maintenance free heavy duty pure electrolytic copper chemical earthing electrode of 50 mm dia., wall thickness 14 gauge and 3 meter length (as per site conditions) with internal strip of copper (25x6)mm along with 60 kg bag of Back fill compound (highly conductive, non-corrosive moisture retaining chemical) complete with excavation , civil works including top 300 mm deep one brick thick masonry chamber & good quality soil, water pouring arrangements with cast iron cover and with arrangements for fitting/termination of G.I. flats/wire with G.I. nut bolts. The voltage between Neutral and earth not to exceed 0 Volts and IR value less than 1 ohm. The earth resistance shall be as per IS 3043.	1	set		
	5	Supply and laying of 6.0 sqmm PVC insulated copper wire from earth station to main panel board in 20 mm GI Pipe including all materials, accessories etc complete.	140	Mtrs.		
	6	L.T.CABLES :				
		Supply,laying ,testing and commissioning of the following 1100 volt grade pvc insulated Al / Cu. Conductor armored cable inner and outer sheathed , along with the two run of G.I.earth wire i/c termination with brass gland and Al. lugs etc. complete as required.				
		On surface :				
		S/Fixing the cable on wall / column / beam / ceiling / above false ceiling / existing trench etc incl. s/f of of saddles / spacers (wherever required as per site conditions) and two run of G.I. earth wire along with the cable. Making good all the damages				
		2 C x 10.0 sqmm armoured copper cable (including earthing wire) for Electric room /Ups room	70	Mtrs.		
	7	TELEPHONE POINT : Supplying, Installation, testing and commissioning of the telephone point with the followings -				
		Two pair, 0.61 mm dia. telephone cable tinned copper conductor, P.V.C. insulated and sheathed , fire retarding, anti				

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

		termite, color coded twisted pairs and rip cord.				
		HMS Pvc pipe on beam /column / wall / flooretc with all necessary materials i/c connections, identification by numbering etc complete as required as per I.T.D. specification.				
		Specifications for item nos. 7(a)&7 (c)				
		Item 7(a)-				
		Single outlet with shutter modular type Telephone Outlets (RJ – 11) with suitable size PVC modular boxes complete as required .	5	Nos.		
	7(b)	7(b) - Providing and fixing 20pair KRONE make telephone tag block with 20 pair module with termination and crimping complete and making good the surface as required/ directed.	1	Nos.		
	7(c)	7 (c) - Providing and fixing 20 pair armoured tinned copper telephone cable in 32 mm PVC conduit as per the Bank's directions from telephone utility junction box - (FOR LEASE LINE etc.)	15	Mtr		
		COMPUTER CABLING SYSTEM- <u>DATA CABELING WORKS.</u>				
	8 a	Supplying, Installation, testing and commissioning of the Computer point with the followings complete in all respect including I/O ports, data cabling, RJ-45 etc. all accessories) -	14	Nos.		
		Four pair CAT 6 LAN cable tinned copper conductor, P.V.C. insulated and sheathed , fire retarding, anti termite, color coded twisted pairs and rip cord. (from server room switch to I/O outlet)				
		HMS Pvc Pipe on beam /column / wall / floor etc with all necessary materials i/c connections, identification by numbering etc complete as required as per At & T specification.				
		Single outlet with shutter modular type I / O's Outlets (RJ – 45) with suitable size PVC modular boxes all complete as required				
	8 b	Supplying and fixing of 12U Rack 3 side open	1	Nos.		
	8 c	Supplying and fixing of 16-Port Cat6 Unshielded Wallmount or Rackmount Patch Panel,	1	Nos.		
	8 d	Supplying and fixing of Patch cord cat6 1 metre B/Y Color	14	Nos.		
	8 e	Supply and Installation of following factory fabricated patch cords (CAT 6) complete with connectors and boots on both sides. Two Meter length	10	Nos.		
	9	<u>WALL BRACKET FAN:</u> Supply and fixing of the following fans MS Wall bracket fan white (400mm blade size)	9	Nos.		
	10	<u>CEILING FAN:</u> Supply and fixing of CEILING FAN 1200 MM Sweep	1	Nos.		

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

		TOTAL (ELECTRICAL, DATA CABLING & ALLIED WORKS) =	
--	--	--	--

Discription	Total Cost (in Rs.)
Civil &Interior Works	
Electricals, Data & Allied Works	
Total Amount	
Total In Words:	

Above rates and amounts are excluding GST and GST as applicable shall be charged extra.