

CIVIL & INTERIOR WORK PART-I					
S.No.	Item/Description	Quantity	Unit	Rate	Amount
3	VITRIFIED TILES: Providing and laying of 600x600,8-10mm thick vitrified tiles inclusive of 4" to 6" skirting of approved make & colours laid on cement mortar (1 cement:4 coarse sand) including pointing of the joints with white cement and matching pigment complete as directed by Architect incharge. Note-The rate also includes providing protection coat of POP with polythene over the tiles till handing over the site. (Color & Shade of Tiles to be pre-approved by Bank)- NEW WORK	200	sqft		
4a	Pantry Platform: Providing and fixing polished and half round moulded edge 18 mm thick (Zed Black) Granite slab (Basic rate Rs.200/- sqft) on the existing pantry platform complete with cleaning of joints and curing.- NEW WORK	5	rft		
4b	Providing & fixing SS sink (min. size 18"x16"x9")- NEW WORK	1	LS		
4c	Plumbing for Sink including all necessary materials & accessories required for the providing the system complete in all respect. Nothing extra to be paid on any account for the said job.- NEW WORK	1	LS		
5	False ceiling Works : Note : i) Rate to be included for all kinds of profiles and cut outs required for light fixtures, Speakers, Smoke detector, trap doors and AC grill in the ceiling. Provision for light fittings, AC grills and diffusers have to be made at no extra cost supported with tees, Angles, etc. suitably fixed all complete as per drawing and direction. The area of these cutouts which is less than 0.5 sqmt for one unit will not be deducted while measuring the ceiling area. ii) The contractor must co-ordinate with electrical & AC contractor for working out various levels for the false ceiling & make the marking on the walls / columns before starting the false ceiling work. <u>Measurement shall be taken of the plan area only, No separate payment will be done for cove or vertical drops.</u>				
5a	PLAIN GYPBOARD FALSE CEILING WITH PAINTING: Providing and fixing suspended false ceiling consisting of 12.5mm thick Gypsum board(India Gypsum) suspended on GI framework. GI framework to consist of GI perimeter channels 0.55mm thick 20mm x 30mm along perimeter of false ceiling of ceiling, screw fixed to wall/partition with nylon sleeves and screws @ 600mm c/c. Suspending GI intermediate channels of size 0.9mm thick 45mm x 15mm from the soffit at max distance 1220mm c/c with ceiling angle 0.55mm thick 25mm x 10mm fixed to soffit using proprietary supplied GI cleats and steel expansion fasteners.Boards to be finished with proprietary supplied jointing tape and jointing compound and sand papered to achieve a smooth and seamless finish and 2 coats of primer alongwith coats of Acrylic paint suitable for Gypsum board upto Bank's Satisfaction .Rate quoted to include vertical all cut-outs required for light fixtures, smoke detectors and other services cut-outs complete as directed by Architect. - RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS	681.97	Sqft.		
5b	GRID FALSE CEILING /Modular False ceiling :Providing and fixing suspended false ceiling consisting : approved make MODULAR CEILING Tile: Classic Lite RH 95; Suspension system Suprafine 15 ()False ceiling will be measured on horizontal plane only. Horizontal plane measurements are to be inclusive of all vertical drops, edge mouldings, fascias, etc.Rate quoted to include all cut-outs required for light fixtures, smoke detectors and other services cut-outs complete as directed by Architect. Rate quoted to include cost of providing support framework formed of perimeter channels for fixing light fixtures, AC grills/diffusers etc. Also to provide concealed perimeter channel support as required to support modular grid ceiling sections at junction between gypboard false ceiling and modular grid tile ceiling - RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS	688.00	Sqft.		
2	Partition &Panelling works (only with HDHMR/EDHMR boards– Century/ Greenply/Archidply). All woods to be treated with anti-termite coating (all sides).The thickness of plyboards/plywoods mentioned below is for boards without laminates.				
	Measurement of height shall be taken from finished floor level up to the level of false ceiling in case of full height partition. In case of low height the measurement of height shall be taken from FFL upto the beading top. In case of varying heights on either side of partition, average heights shall be considered. The rate to include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc, making provision for laying conduct as per drawings and directions of site Eng. / Architect. It also includes beech wood /mdf properly polished top beading on all sides as per the requirement of specified size as per the directions of Engineer. All wood frame work to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti-termite properties. The work also includes provision of door as per requirements along with all lock (Godrej) Handle, Hinges (5.5) stoppers, door closures etc. as per bank's architect instructions. The rate also includes at no extra cost providing extra framework support above false ceiling upto RCC slab at every 4ft or less distance so as to make entire full height solid/glazed/semi-glazed partition rigid and firm.				

a	<p>Providing and fixing solid partition / glazed partition from floor level up to the level of false ceiling with frame work of aluminum with sections 1.75" x 1.75" at spacing not exceeding 600mm center to center in vertical direction. (Vertical member to be in one piece) and horizontal direction with 7 mm or more thick boards to be fixed on both sides, including grooves as per instructions and 1.0 mm thk laminate to be fixed (both sides) on top complete with polishing / painting the beading surface with spirit polish as per design and to the satisfaction of Architect/Employer. For glazed partition - ations as (3A) item also includes 10mm Etched/frosted Glass above 900 mm to 1350/1800/2100/2400/2700 mm fixed in 75x15 mm beading as per specifications fixed around opening finished with melamine matt polishing. Rest of specifications same as MAIN specifications of Partitions. Complete to the satisfactions of Architect/ Bank - RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS</p>	695.00	Sqft.		
b	<p>Providing and fixing Low height partition from floor level up to the 1220/1540mm with frame work of aluminium 1.75" x 1.75" at spacing not exceeding 600 mm center to center in vertical direction (Vertical member to be in one piece) and horizontal direction, 7 mm or more boards to be fixed on both sides, including grooves as per instructions and 1.0mm thick laminate to be fixed on top. 15 mm beech wood molding on top and side edges of partition and including 12 mm etched glass above 900 mm in straight / taper or curved shape as detailed, complete with polishing/paining the grooves as per design and to the satisfaction on Architect / Bank. - RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS</p>	64.00	Sqft.		
c	<p>Providing and fixing wall panelling as per design & pattern with atleast 1.5"x 1" aluminum frame at 2'-0" c/c in both directions with 7mm or more thick boards on top and finished with 1.0 mm laminate. The panelling to be screwed to the frame work; as per design and details. The wood surfaces to be finished in melamine polish complete. Top of the paneling edges / is to be provided with laminate or beech wood wood decorative beading of 35mm x 15 mm finished with polish/painting as directed. - RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS AFTER LAYING AC COPPER AND DRAIN PIPE BEHIND THE PANNELLING</p>	834.00	Sqft.		

d	Providing and fixing cash cabin partition from floor level up to the level of 2100 mm (approx.) with same specification as above at serial no. (a), (b) but with a 12 mm thick etched glass / tapered glass from 1067 up to 2100 fixed in beech wood wood beading of the size 35x15 mm over aluminum frame of size 10x25 screwed to the frame work: as per design and details. The wood surfaces to be finished in melamine polish complete. The item also includes cash cabin door with required hardware, accessories, door closure, handle, lock etc. which will be measured as partition.- RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS	204.90	Sqft.		
e	Providing and fixing 12mm ETCHED float glass in FRONT of CASH CABINS with metal clamps and all required accessories over existing partition including cutouts for passing currency as per details in item no. 3 (e). The edges of the glass to be polished complete with necessary cutting the holes in shape properly, grinding & polishing.- NEW WORK	50.00	Sqft.		
f	FULL HEIGHT 12MM THK. TOUGHEN GLASS PARTITION: P/F 12 mm thick toughened glass full height glass embedded in aluminum anodized sections all around for external / internal glazing. Anodizing to be Natural Finish shade. (as per Bank's approval).(Frame work details as mentioned in item no. 2 above) The works includes fixing of glass with Top & Bottom surfaces with proper support/frame.- NEW WORK	20.00	Sqft.		
3	Doors - NEW WORK				
a	Providing and fixing of toughened glass doors (min. 12mm) with below fixtures of size 750x 2100 mm (approx.)	2.00	Nos		
	Door Lock				
	Door stopper				
	Floor Machine (design as per load) - Ozone, Hardwyn, Dorset				
	Parch fitting				
	S.S. Handle 12" long				
b	Providing and fixing (FLUSH SOLID / GLAZED DOOR) – Doors- Providing and fixing single leaf solid core / GLAZED flush door min 35mm thick factory made, finished on both sides with 1.0mm thick laminate of approved shade as indicated in drawing. Shutter to be lipped on all sides with 12mm thick teak wood beading. Applicable hardwares to be considered for following doors according to requirement as per detailed drawings including below mentioned hardware-Door closer,SS Ball bearing Hinges ,SS foot operated Door stopper,SS Mortise Latch Lock / concealed dead lock,SS Mortise Handle. All material is of approved brand. approx size of door 750 x2100 - NEW WORK	3.00	Nos		
c	Flap door: P/F 4' x 3' matching 19mm laminated plyboard flap door.- NEW WORK	3.00	nos		
4	Miscellaneous				
a	ACP Shutter Box: Rolling shutter boxing made up in ACP (min 3mm thick) with required frameworks with all accessories as per Architects approval. Measurement to be considered for all sides for work complete in all respect.- NEW WORKS	45.00	Sqft.		
b	ELECTRICAL CABINET(all inside structure only with HDHMR/EDHMR boards– Century/ Greenply/Archidply; for shutters 19mm plyboard with Greenply (ecotec) / Century (sainik) / Archidply (classic)): Providing and fixing the 1'-6" deep storage units. The storage units shall have shutters made in 17mm or more thick boards and finished in laminate of approved shade including top. Laminate to be provided in 1 mm thickness (exterior) and 0.8 mm thick (interior)- no paint. Backply to be in 7 mm or more boards.The storage units shall have intermediate shelves as per DB sizes made in 17mm or more thick boards with matching wood lipping. The storage shall have matching wood edge molding as per the detail drawings. This also includes providing necessary hardware like handles, hinges, locks, tower bolts etc. of approved make. All exposed wooden surfaces shall be stained to shade. Louvers to be provided in shutter as per the design / instructions of Bank. - NEW WORK	45.00	Sqft.		
c	FILE STORAGE CABINETS(all inside structure only with HDHMR/EDHMR boards– Century/ Greenply/Archidply; for shutters 19mm plyboard with Greenply (ecotec) / Century (sainik) / Archidply (classic)): Providing and fixing the 1'-6" deep storage units. The storage units shall have shutters made in 17mm or more thick boards and finished in laminate of approved shade including top. Laminate to be provided in 1 mm thickness (exterior) and 0.8 mm thick (interior). The storage units shall have intermediate shelves in 17mm or more thick boards with matching wood lipping. Backply to be in thickness 7mm or more thickboards.The storage shall have matching wood edge molding as per the detail drawings. This also includes providing necessary hardware like handles, hinges, locks, tower bolts etc of approved make. All exposed wooden surfaces shall be stained to shade. All exposed wooden surfaces shall be stained to shade. (same for Over Head storage required above Pantry counter.)- RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS	462.80	Sqft.		
d	CHEQUE DROP BOX : (2'-0" x 3ft High X 10" deep) Providing and fixing cheque drop boxes made out of 19mm thk. Commercial plywood grade I finished with 1mm thk. Laminate. Slit should be provided to drop cheques and opening provided with locking arrangement to remove cheques, complete in all respect. - NEW WORK	1.00	Nos.		
e	WRITING TABLE: Writing desk made of wood with glass top as per Design Size: 30"x1'0" minimum. Writing Ledge to have facility of pigeon holes beneath to place the pay in / payout slips etc. - NEW WORK	1.00	nos		
5	FURNITURE				

	<p>FURNITURE [only with HDHMR/EDHMR boards– Century/ Greenply/Archidply. All Tables / counters/ work stations to have 17mm or more thick boards top and sides to be with 17 mm or more boards and 1.0 mm laminate finish on exposed surfaces with 0.8 mm thick laminate inside/all the surfaces instead of painting the surfaces / area, drawer units is to be made from 17 mm or more one side boards with 1.0 mm laminate finish. The drawers to run on telescopic drawer channels. Drawer units to have two smaller and one bigger drawers and locking arrangement (Godrej, ozone, dorma). Foot-rest 75x50mm 2nd class cedarwood member to be fixed for each table the rate to include all hardware such as drawer channels, SS handles etc. The inside of the table to be provided with 0.8 mm thick laminate (White cream shade). The item also includes a tray for key board running on telescopic channel (ozone/hettich), finished with laminate on top and rounded front size 560x450 readymade CPU trolley with castors etc. complete. (EBCO make)</p>				
	<p>All Tables / counters/ work stations to have 17mm or more thick boards top and sides to be with 17 mm or more boards and 1.0 mm laminate finish on exposed surfaces with 0.8 mm thick laminate inside/all the surfaces instead of painting the surfaces / area, drawer units is to be made from 17 mm or more thick boards for the front and rear, 11 mm or more boards for sides and 7mm or more thick boards for the bottom with 1.0 mm laminate finish. The drawers to run on telescopic drawer channels. Drawer units (approx. size-400x450x680) to have two smaller and one bigger drawers (or storage below one drawer as required by Bank) and locking arrangement (Godrej, ozone, dorma, hettich). Foot-rest 75x50mm 2nd class cedarwood member (polished) to be fixed for each table the rate to include all hardware such as drawer channels, SS handles etc. Front modesty with 17 mm or more thick boards and 1 mm laminate as per designed in straight / curved shape. The inside of the table to be provided with 0.8 mm thick laminate (White cr)</p> <p>ded front size 560x450 readymade CPU trolley with castors etc. complete. (EBCO make)above false ceiling upto RCC slab at every 4ft or less distance so as to make entire full height solid/glazed/semi-glaze</p>				
a	<p>Providing and fixing Manager Table as per main specification but finished in 1 mm laminate in two or more colors. The table size to be 1800x750x750 mm. The item also includes Side cupboard for B.Manager with Laminate finish as per the specifications / design by Bank with size 900x450x750.-</p> <p>RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS</p>	1	nos		
b	<p>Providing & placing in position BANKING COUNTER TABLE with 750 high x 750MM wide made of 17 mm or more thick boards working top front in straight / curved shape and 1.0 mm laminate finish on exposed surfaces with 0.8 mm thick laminate inside/all the surfaces instead of painting the surfaces / area. Counter items also includes Front modesty with 17 mm or more thick boards and 1 mm laminate as per designed in curved shape as shown in drg. Drawer units to be as specified in MAIN specifications. BUT with divisions for currency as per BANK's instructions, The drawer units to have AUTOLOOKING system for drawers (Godrej). One footrest per occupant, key board tray 560x450 laminate finish, CPU stand All as per MAIN Specifications for tables, counter is finished with 0.8 mm thick laminate (white/cream) inside the counters & drawer units etc, complete to the satisfaction of Architect/Bank. -</p> <p>RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS</p>	25	rft		

c	Providing and placing in position Cash Counter Table made from 17 mm or more thick boards and with 1mm laminate finish, with overall height of 1050 mm for working counter at 750mm and customer counter at 1050 mm height made with 300mm wide 19 mm comm board finished in 1 mm laminate. Counter items also includes Front modesty with 17 mm or more thick boards and 1 mm laminate as per design. The Counter to have drawer units same as mentioned in Main specifications of Tables above except the drawers to have divisions as per Bank's instructions. The counter to have 1 footrest per occupant. Item also includes a key-board tray & C.P.U. stand for EARL Bihari/ ebcomake. The inside of the table to be 0.8 mm thick laminate (white/cream) complete to the satisfaction of Architect/Bank.- RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS	10	rft		
d	SERVER ROOM TABLE (Size - 1200 x 700 x 750): All as per MAIN Specifications for tables / counter without drawers complete to the satisfaction of Architect/Bank. No Storage drawer is to be provided.- RATE TO BE QUOTED ONLY FOR BALANCE WORK TO BE COMPLETED FOR ABOVE SPECIFICATIONS	1	Nos		
				Total=	