



ई-निविदा प्रपत्र – फ़ाइनेंषियल बीड
सेंट्रल बैंक ऑफ़ इंडिया के
317 एम जी मार्ग, पुणे स्थित
आंचलिक कार्यालय भवन का
स्ट्रक्चरल ऑडिट करने के लिए कंसल्टेंट की नियुक्ति हेतु

निविदाकार का नाम :- _____

निविदा प्रस्तुत करने की अंतिम तिथि: 25/08/2025 दोपहर 03:00 बजे तक

निविदा खोलने की तिथि (केवल प्रि-क्वालीफिकेशन/टेकनिकल निविदा) : 25/08/2025 दोपहर 03:30 बजे

निविदा शुल्क: डिमांड ड्राफ्ट के रूप में ₹2,000 (₹ दो हजार मात्र) अप्रतिदेय

बयाना जमा राशि: डिमांड ड्राफ्ट के रूप में ₹ 5000.00 (₹ पाँच हजार मात्र)

सेंट्रल बैंक ऑफ़ इंडिया,
व्यवसाय सहायता विभाग
पहिली मंजिल आंचलिक कार्यालय
317 एम जी मार्ग, कैप
पुणे 411001
दूरभाष:- 020-26131611-14



e-Tender Document – Financial Bid

For

Consultancy and Conducting of Structural Audit and NDT of Bank's Buildings at 317, M G Road, Camp, Pune 411001

Name of the Tenderer: - _____

Last Date of Submission: 25/08/2025 at 3.00 PM

Date of Opening of Pre-Qualification/Technical bid: 25/08/2025 at 3.30 PM

Tender fee: ₹ 2,000.00 non-refundable in the form of DD

Earnest Money Deposit: ₹ 5000.00 DD in favor of Central Bank of India, Payable at Pune

CENTRAL BANK OF INDIA,
General Administration Department,
1st floor, Zonal Office,
317, M G Road, Camp,
Pune 411001
Ph: - 020-26131611-14



PART II (Financial Bid)

Name of the Work: Consultancy and Conducting of Structural Audit and NDT of Building of Central Bank of India, at **317, M G Road, Camp, Pune 411001**

Sn o	Description	Quantity	Unit	Rate (₹)	Amount (₹)
1	Conducting detailed visual survey of building (internally and externally) by visual inspection to record observation of distressed part of building, level of deterioration)	LS	LS		
2	NDT				
	The total no's would be decided after inspection of the property in consultation with Bank Officer In charge (not less than 20 nos/ locations per floor).				
a	Rebound Hammer Test: Preparing the Surface of RCC Structural Members such as beams, columns, slabs etc by chipping the plastered surface/finishing/cladding to expose the concrete, smoothing the area using carborandum stone all in terms of relevant IS Code and conducting rebound hammer test all as per IS 13311-1992(Part2) or as directed by the Engineer In charge including analysis of the test result and preparation of report with observations and recommendations for remedial measures if any.	Total Carpet area 2750.00	Sq.m		
b	UPV(Ultrasonic Pulse Velocity) Test: Preparing the surface of RCC Structural Members such as beams, columns, slabs etc. by chipping the plastered surface/finishing/cladding to expose the concrete, smoothing the area using carborandum stone all in terms of relevant IS Code and conducting UPV test as per relevant standard or as directed by Engineer in charge including analysis of the test result and preparation of separate report for each building with observations and recommendations for remedial measures if any.	2750.00	Sq.m		
c	Half Cell Potential Test for Corrosion mapping. Preparing the structural members as directed to expose the Reinforcement steel, cleaning the area with blower/wire brush and carrying out half-cell potentiometer test for measuring the level of corrosion of reinforcement steel in the RCC member including analysis of the test result and preparation of separate report for each building with observations and recommendations for remedial measures if any.	2750.00	Sq.m		

d	Carbonation Depth Test :Preparing the surface of RCC structural member such as beams, columns, slabs, water tank walls and slab etc. by chipping the plastered surface/finishing/cladding to expose the concrete, cutting etc. as per relevant code and conducting carbonation test at various depth as directed Engineer In charge using phenolphthalein of specified concentration to assess depth of carbonation including separate report for each building with analysis of the test result and preparation of remedial measures if any observations and recommendations.	2750.00	Sq.m		
3	Consultancy charges for preparation of structural audit report which includes:	1	LS		
a	The findings from detailed visual inspection as in item 1				
b	Non Destructive Test Results				
c	Suggested remedial measures				
d	Bill of quantities item wise and detailed specification with cost estimate for the building				
e	Classification of severity				
f	Photos of Distressed Location				
4	Intermittent visits of site during rectification work in consultation with Bank Officer in charge and final certification of rectification work completed by the contractor (This part of fees is applicable only if major structural remedial/rectification work is required to be done)				
	TOTAL				
	GST				
	G. TOTAL				

(Amount in Words:)

NOTE:

1. Repairing of damages caused during conducting of the above said tests shall have to be rectified by the consultant at his/ her own cost.
2. The rates quoted shall be inclusive of all scaffolding, hoists, hoisting equipment, tools, equipment's, testing equipment's etc., required for the smooth execution and completion of the work.
3. The consultants/Firms should visit the site to understand the scope of work before quoting

Place:

Date:

Signature & Seal of the Tenderer